Cobourg East Community Secondary Plan Area Municipal Servicing Class EA

Public Information Centre – February 8, 2023



Cobourg East Development Owners Group



Land Acknowledgement

We respectfully acknowledge that we are located in the traditional and treaty territory of the Michi Saagiig (Mississauga) and Chippewa Nations, collectively known as the Williams Treaties First Nations, which include: Curve Lake, Hiawatha, Alderville, Scugog Island, Rama, Beausoleil, and Georgina Island First Nations.

We respectfully acknowledge that the Williams Treaties First Nations have been stewards and caretakers of these lands and waters, and that today remain vigilant over their health and integrity for generations to come.

We are all Treaty people.

Project Team

Co-Proponents

Town of Cobourg



Terry Hoekstra, C.E.T., LET, rcca Project Manager Town of Cobourg

Cobourg East Development Owners Group (Tribute Communities and Mistral Land Development)

Consultants

CIMA+



Why Are We Here?

Purpose of the Public Information Centre (PIC)

- 1. Introduce the study
- 2. Outline the Class EA process and study schedule
- 3. Review background information and existing conditions
- 4. Evaluation of alternatives and selection of the recommended alternative solution
- 5. Obtain community and public feedback and identify next steps

How to Get Involved



Review the information in this presentation




Provide comments and feedback



Join the study mailing list or contact the Project Team

Overview of Schedule 'B' Municipal Class EA Process & Consultation


The study is following the Municipal Engineers Association (MEA) **Municipal Class Environmental Assessment** (Class EA) process for **Schedule B** projects (October 2000, as amended 2015).



Project Background & Study Area

The Town of Cobourg and the Cobourg East Development Owners Group have initiated a Municipal Class EA Study to provide wastewater and water servicing infrastructure that will support future development of lands within the Cobourg East Community Secondary Plan Area (Cobourg East).


The municipal wastewater and water trunk services will be designed to extend and support the full build-out needs of Cobourg East for ongoing and future developments.






Cobourg East Development Owners Group – Landownership Map


Cobourg East Secondary Land Use Plan




Project Constraints - Existing Conditions



Proposed Alternatives – Wastewater Servicing




Proposed Alternatives – Water Servicing



Screening of Alternative Wastewater Solutions

- Alternative Solution WW4 (Gravity Sewer Normar Rd./Workman Rd.) was screened out at the beginning of the evaluation due to the following:
 - Difficult to service the development area from the easterly side of study area;
 - To service the development via gravity, the sewer along this alignment would have to be constructed at depths between 23 m to 36 m deep;
 - To construct the sewer at these proposed depths, it can only be done using tunneling methods; and
 - There would be a significant cost to constructing a sewer by tunneling.



Alternative Sanitary Servicing Solutions

- For portions of the alignment the only solution is following Brook Rd N from north of the railway line to the electrical substation and then west from the intersection of Elgin St E and Brook Rd N to the Study Area boundary.
- There are two areas that require evaluation and selection of a recommended alternative:
 - 1. Southern portion which includes solutions WW1, WW2 and WW3 representing different options for crossing the Railway Line and connecting with the existing sanitary sewer on Thompson St.
 - 2. Northern portion which includes WW1A, WW1B and WW1C which represents the area from the electrical substation to the intersection of Brook Rd N and Elgin St E.
- The recommended wastewater alternative solution will be a combination of the alignment WW1, WW2, or WW3 (from Thompson Street to Brook Road North (north of the railway line)) + Brook Road North up to the electrical substation + WW 1A, 1B or 1C (from electrical station to Elgin Street East) + Elgin Street East (from Brook Road North to the Phase 1 Interim Solution).
- Evaluation of the **Do Nothing** wastewater option has not been included in the evaluation table since the Do Nothing does not provide wastewater servicing that will support future development of lands within the Cobourg East Community Secondary Plan Area (Cobourg East).

Selecting the Recommended Alternative Solution: Detailed Evaluation Criteria


The criteria shown below were used to evaluate the alternative solutions.



Wastewater Servicing Alternative Solutions - South Portion

Alternatives from Electrical Substation to Thompson Street

- Alternative WW 1 Gravity Sewer – Railway / Brook Road North
- Alternative WW 2 Gravity Sewer – King Street East / Brook Road North
- Alternative WW 3 Pumping Station and Forcemain – King Street East / Brook Road North



Evaluation of Wastewater Servicing Alternatives - South Portion

From electrical substation to Thompson Street		Most Less Preferred Prefe	erred Preferred
Evaluation Criteria	Alt. WW1	Alt. WW2	Alt. WW3
Natural Environment	 Creek crossing through trenchless technology (no in-water work) Construction stays within Brook Road N and Willmott Street ROW 	 Creek crossing through trenchless technology (no in-water work) Construction stays within Brook Road N, King Street E and Willmott Street ROW 	 Creek crossing through trenchless technology (no in-water work) Construction stays within Brook Road N, King Street E and Willmott Street ROW
Social and Cultural Environment	 Lower construction impacts by crossing disturbed development lands (north of CN/CP Railway) and Wilmott Street Greater construction related impacts on Brook Road N 	 Greater construction impacts on Brook Road N and King Street E and within built-up area Larger portion of lands within existing urban environment (south of CN/CP Railway) 	 Forcemain and pumping station results in greater construction impacts on Brook Road N and King Street E and within built-up area
Technical Considerations	 Majority is gravity sewer making it more resilient Constructed via open cut trench methods, trenchless methods at railway and creek crossing 	 Majority is gravity sewer making it more resilient Constructed via open cut trench methods, trenchless methods at railway and creek crossing Significant construction constraints on King Street E 	 Gravity sanitary sewer, pumping station and forcemains – less resilient Constructed via open cut trench methods, trenchless methods at railway and creek crossing Significant construction constraints on King Street E


Evaluation of Wastewater Servicing Alternatives - South Portion

•	From electrical sub	station to Thompson Street	Most Less Preferred Prefe	
	Evaluation Criteria	Alt. WW1	Alt. WW2	Alt. WW3
	Financial Considerations	 Lower capital costs and low operating/maintenance costs Development lands required 	 High capital costs with low operating/maintenance costs No land acquisition required 	 Highest capital, operating/ maintenance costs with forcemain and pumping station Land required for pumping station
	Overall Rating	Preferred	Less Preferred	Least Preferred

Wastewater Servicing Alternative Solutions - North Portion

Alternatives from Elgin Street East to Electrical Substation

- Alternative WW 1A Gravity Sewer, Trench Installation
- Alternative WW 1B Gravity Sewer, Tunnel Installation
- Alternative WW 1C -Gravity Sewer to pumping station, forcemain over the drumlin, outlet to gravity sewer, Trench Installation



Evaluation of Wastewater Servicing Alternatives – North Portion


From Elgin Street East to electrical substation		Most Less Least Preferred Preferred Preferred	
Evaluation Criteria	Alt. WW#1A	Alt. WW#1B	Alt. WW#1C
Natural Environment	 Creek crossing through trenchless technology (no in-water work) Marsh and unevaluated wetlands present but these are located on disturbed lands that will be developed 	 Creek crossing through trenchless technology (no in-water work) Construction stays within Elgin Street E and Brook Road N ROW 	 Creek crossing through trenchless technology (no in-water work) Construction stays within Elgin Street E and Brook Road N ROW with minimal impacts
Social and Cultural Environment	 Undeveloped lands impacted Some construction impacts along Elgin Street E 	Construction impacts along Brook Road N and Elgin Street E	 Shallow forcemain results in greater construction impacts on Brook Road N and Elgin Street E Land required and potentially impacted for pumping station
Technical Considerations	 Gravity sewer making it more resilient Open cut trench construction around the drumlin 	 Gravity sewer making it more resilient Sewer required to be constructed via tunnelling methods through the drumlin on Brook Road N 	 Space required to construct pumping station, forcemain constructed via open trench method along Brook Road N through the drumlin Sewer system requires pumping station and forcemains – less resilient

Evaluation of Wastewater Servicing Alternatives – North Portion

From Elgin Street East to electrical substation		Most Less Least Preferred Preferred Preferred	
Evaluation Criteria	Alt. WW#1A	Alt. WW#1B	Alt. WW#1C
Financial Considerations	 Lowest capital costs and low operating/maintenance costs Land required from development lands 	 Higher capital costs with depth of gravity sewer but low operating/maintenance costs No land acquisition required 	 High capital, costs and higher operating/ maintenance costs with forcemain and pumping station Land required for pumping station
Overall Rating	Preferred	Less Preferred	Least Preferred

Water Servicing Alternative Solutions

• There was only one alternative to the "Do Nothing" Alternative which is to build the feedermain from the proposed elevated water tower to Brook Road North.



Evaluation of Water Alternatives

Most Preferred

Least Preferred

Evaluation Criteria	Alternative #1	Do Nothing
Natural Environment	 Crosses through recreational fields, Buckthorn deciduous shrub thicket and Willow Lowland deciduous forest 	No construction related impacts
Social and Cultural Environment	Air and noise impacts during construction with minimal effect on industrial business and recreational fields	No construction related impacts
Technical Considerations	 Constructed via open cut trench methods with minimal dewatering impacts due to shallow bury of minimum 1.8 m depth Watermain will provide main supply of expanded water supply system 	 Does not provide water servicing to development areas and does not meet problem statement No resiliency provided
Financial Considerations	 Some land needs to be provided from development lands Approximately \$500,000 capital costs and minimal operating and maintenance costs 	 No capital costs but inability to provide water services to development areas is a cost to the Town
Overall Rating	Preferred	Least Preferred

Recommended Preferred Wastewater Alternative Solutions

- For the Wastewater Servicing the recommended preferred alternative for the south portion is:
 - Alternative WW 1 Gravity Sewer
 - Railway / Brook Road North




- For the Wastewater Servicing the recommended preferred alternative for the north portion is:
 - Alternative WW 1A Gravity Sewer, Trench Installation



Recommended Preferred Water Alternative Solution

For the Water Servicing the recommended preferred alternative is:

 Feedermain from Elevated Tank to Brook Road North



Proposed Mitigation Measures

Concern	Proposed Mitigation Measure(s)
Railway Crossings	- Use trenchless technologies
Creek Crossings	- Use trenchless technologies
Erosion and Sedimentation	 Erosion control measures Buffers and setbacks Sediment traps Staging work
Traffic Impacts	 Staging of construction to cause least disruption Notify public and adjacent landowners of construction scheduling
Private Well Impacts	- Conduct well monitoring program with intent to rectify any impacted wells
Dust & Noise	 Employ noise and dust control measures Staging of construction to cause least disruption
Maintenance & Operation	 Construct access roads to maintenance access structures outside of road right-of-ways Provide sufficient setbacks from adjacent infrastructure and foundations

Next Steps – Please Stay Engaged

Please submit any comments or feedback on the PIC by **Wednesday, February 22, 2023**.

After the PIC, the Project Team will:

- Review and consider input received during the PIC
- Confirm the recommended alternative solution to provide the preferred alternative for water and wastewater.
- Prepare the Project File Report.
- Issue the Notice of Completion when the Project File Report is available for a 30-calendar day public comment period.

Thank You for Attending!

Project Information

• For more information about this project, please visit our webpage:

https://www.cobourg.ca/en/townhall/Reports-Studies-and-Plans.aspx



 Should you have any questions or comments at any time during the project, please contact:

Terry Hoekstra, C.E.T., LET, rcca thoekstra@cobourg.ca Town of Cobourg Project Manager Chad Stephen, P.Eng., PMP chad.stephen@cima.ca CIMA+ Project Manager