

The Corporation of the Town of Cobourg
Boardwalk Material Supply
Contract No. CO-23-17-PWD
Addendum No. 2

This Addendum issued December 1, 2023 forms part of the Contract Documents and Specifications for the above-noted Contract and shall be read in conjunction therewith. This addendum shall take precedence over all requirements of the original plans and tender documents issued previously. The Bidder must acknowledge receipt of this Addendum on Appendix B of the Request for Quotation Package.

No. of Addendum Pages: 1

No. of Attachments: 1

Purpose:

The purpose of this addendum is to provide further clarification of the requirements as outlined in Request for Quotation CO-23-17-PWD.

Closing Date:

The closing date has been extended to **Thursday, December 7, 2023 at 2:00 P.M.**

Appendix C Pricing:

The pricing form is re-issued with all product sizes and quantities indicated. Please note that actual quantities to be supplied may be adjusted, and will be confirmed with the successful bidder prior to ordering.

The Bidder shall sign this Addendum in the space provided below and shall submit this Addendum in the same envelope as the quotation.

Except as and to the extent that they are amended by the foregoing, all terms and conditions of the original Request for Quotation documents remain in full force and effect.

Company Name

Signature of Bidder

Request for Quotation CO-23-17 PWD: 2023 Boardwalk Material Supply

1. For nominal sizes that are blank the supplier shall indicate the size proposed based on the performance of the proposed material to meet the required loading requirements.
2. For quantities that are blank the supplier shall indicate the quantity proposed based on the spacing required for the proposed material to meet the required loading requirements.
3. For lump sum (LS) items the supplier shall include an price sufficient to provide the quantity required based on the size and spacing of the proposed material and the connection details.

	Description	Nom. Size (1)	Nom. Length	Quantity (2)	Unit of Measure	Unit Price	\$ Total for 1 Section	# of Sections	\$ Total Extended to All Sections
HDPE Framing Lumber									
1	Members in 5-Ply Sleeper (one sleeper per section)	2 x 8	144 in	5	each			225	
2	Members in 3-Ply Intermediate Sleeper (if required)	2 x 8	144 in	0	each			225	
3	Members in 2-Ply HDPE Outside Stringer	2 x 8	96 in	4	each			225	
4	Interior Stringer	2 x 8	96 in	8	each			225	
5	Mid-span Blocking (to be cut from)	2 x 8	144 in	1	each			225	
Pressure Treated Framing and Decking Lumber									
6	End Cap	2 x 8	144 in	2	each			225	
7	Deck Board	2 x 6	144 in	17	each			225	
8	Pressure Treated Curb Support Block (6" length)	2 x 4	96 in	0.5	each			225	
9	Pressure Treated Curb	2 x 4	96 in	2	each			225	
Fasteners & Other Hardware									
10	Structural Screw (Sleeper Lamination)	3/8 in dia.	7-1/4 in	30	each			225	
11	Galvanized Lag Bolt	3/8 in dia.	5 in	10	each			225	
12	Galvanized Carriage Bolt	1/2 in dia.	4 in	2	each			225	
13	Framing Screw (Stringer Connection to Sleeper) - at Fixed End Only	#10	3-1/2 in	100% (3)	LS			225	
14	Framing Screw (End Cap Connection to Stringer)	#10	3-1/2 in	100% (3)	LS			225	
15	Framing Screw (Outside Stringer Lamination)	#9	2-1/2 in	100% (3)	LS			225	
16	Framing Screw (Blocking Connection to Stringer)	#9	2-1/2 in	100% (3)	LS			225	
17	Coated Wood Screw (Decking Connection to Stringer)	#8	3 in	100% (3)	LS			225	
18	Coated Wood Screw (Curb Support Connection)	#10	4 in	100% (3)	LS			225	
19	Washers and Other Miscellaneous Hardware	Varies	Varies	100% (3)	LS			225	
								Subtotal	
								HST	
								Total (Including HST)	