ZONING DATA CHART

GROSS SITE AREA: 12,781 m² ASPHALT AREA: 9,755 m²
BUILDING AREA (TOTAL): 2,492 m² LANDSCAPED AREA: 1,301 m²
EXISTING 1,858 m²
PROPOSED 634 m²

ITEM	SC-1*	REQUIRED	PROVIDED
1	PERMITTED USES	SEE PERMITTED USE NOTE ON SHEET SP1	SEE PERMITTED USE NOTE ON SHEET SP1
2	LOT AREA (ACRES MIN)	1.3	3.2
3	LOT FRONTAGE (m MIN)	60	62.95
4	FRONT YARD EXTERIOR SIDE YARD SETBACK (m)	3.0 MIN 15.0 MAX	7.45 FRONT N/A EXTERIOR SIDE
5	REAR YARD (m MIN)	9.0 ABUTTING RESIDENTIAL 6.0 ABUTTING OTHER	46.67 N/A
6	INTERIOR SIDE YARD SETBACK (m MIN)	9.0 ABUTTING RESIDENTIAL 6.0 ABUTTING OTHER	N/A 0*
7	LANDSCAPED OPEN SPACE (%) MIN	10	10.2
8	LOT COVERAGE (%) MAX	35	19.6
9	HEIGHT MAXIMUM (STOREYS MAX)	4	1
10	GROSS FLOOR AREA (m² MAX)	N/A	2,510
11	LOADING SPACE REQUIREMENTS	SEE LOADING REQUIREMENTS NOTE	SEE LOADING REQUIREMENTS NOTE
12	VEHICLE PARKING	SEE PARKING REQUIREMENTS NOTE	SEE PARKING REQUIREMENTS NOTE

* EXISTING CONDITION

PERMITTED USES

SC-1 ZONE (SITE SPECIFIC BY-LAW No. 85-2003):

- CALL CENTRE;
- CLINIC USE;
- CONFERENCE CENTRE;
- CONVENIENCE COMMERCIAL USE;
- CONVENTION USE;
- DATA PROCESSING USES;
- DAY NURSERY USE;
- **EATING ESTABLISHMENT USE, INCL. BANQUET HALL;**
- EDUCATION AND TRAINING USE;
- FINANCIAL INSTITUTION USE;
- FOOD AND/OR SPECIALTY FOOD USE, INCL. SUPERMARKET AND BAKED GOODS OUTLET;
- HOTEL AND MOTEL USE;
- INSTITUTIONAL USE;
- OFFICE USE;
- PARKS AND RECREATION USES;
- PERSONAL SERVICE USE INCL. A DRY CLEANING DISTRIBUTION STATION, BUT NOT A DRY CLEANING ESTABLISHMENT;
- PLACE OF ENTERTAINMENT USE;
- PRIVATE OR COMMERCIAL CLUB USE;
- PUBLIC USES IN ACCORDANCE WITH THE PROVISIONS OF SECTION 5.3.2;
- **RETAIL COMMERCIAL USE, INCL. DEPARTMENT STORE AND CATALOGUE STORE;**
- VEHICLE SERVICE STATION;
- VEHICLE SERVICE AND SUPPLY USES;
- WHOLESALE USES

LOADING ZONE REQUIREMENTS

*LOADING SPACES MUST BE MINIMUM 4.5m WIDE WITH VERTICAL CLEARANCE OF 4.25m FOR CSA ZONING

TOTAL SPACES REQUIRED ON LOT (TWO BLDGS 0-2,350m²) = 2 SPACES REQUIRED
TOTAL SPACES PROVIDED ON LOT = 2 SPACES PROVIDED*
(*MINOR VARIANCE REQUIRED)

PARKING REQUIREMENTS (AREA 3):

MINIMUM PARKING SPACE DIMENSIONS 15.05m², TYPE A 3.4mX5.5m, TYPE B 2.4mX5.5m

SHOPPING CENTRE (EXISTING)	5.5/100m²	1,858m²	= 103 SPACES
EATING EST. (PROPOSED)	1/9m²	204m²	= 23 SPACES
RETAIL COMMERCIAL (PROPOSED)	1/18m²	430m²	= 24 SPACES
TOTAL REQUIRED PARKING			= 150 SPACES
TOTAL PROVIDED PARKING (INCL. 10 CAR STACKING)			= 166 SPACES
B/F PARKING: 1/20 FOR 1ST 100 + 1/ADDITIONAL 100 REQUIRED			= 6 SPACES
PROVIDED			1 TYPE 'A', 2 TYPE 'B' + 2 EXISTING

NOTE:

REFER TO OBC MATRIX PREPARED BY PATRICK TROTTIER ARCHITECT, PROVIDED SEPARATELY.

WASTE REMOVAL

GARBAGE TO BE STORED EXTERNALLY IN DEEP WELL GARBAGE CONTAINERS AND OWNER TO ARRANGE SITE PICK-UP AND REMOVAL.

BUILDING CLASS

COMMERCIAL - GROUP E OCCUPANCY, PART 3 OF THE ONTARIO BUILDING CODE

CANADA POST

THIS DEVELOPMENT WILL RECEIVE MAIL TO A NEAR-BY SUPERBOX AS LOCATED BY CANADA POST.

LEGEND

- FR-2 — PROPOSED SIGN, TYPE OF SIGN
- PFFE* — PRINCIPAL FIRE FIGHTER'S ENTRANCE
- PROPOSED BARRIER FREE ROUTE
- PROPOSED FIRE ROUTE (6.0m WIDE, 12.0m ℄ RADIUS)
- ® — PROPOSED RAMP (SEE DETAIL ON SP2)
- BUILDING ENTRANCE
- PROPOSED LIGHT-DUTY ASPHALT
- PROPOSED HEAVY-DUTY ASPHALT
- PROPOSED CONCRETE
- EXISTING BUILDING
- PROPOSED BUILDING
- LIMITS OF SUBJECT PROPERTY

REFERENCE DOCUMENTS

1. TOPOGRAPHICAL SURVEY PREPARED BY SBMG, FILE. NO SBMG-21-0065, DATED APRIL 20, 2021.
2. CONCEPTUAL SITE PLAN PROVIDED BY WESTDELL DEVELOPMENT CORPORATION RECEIVED MARCH 18, 2021.
3. DESIGN BRIEF PREPARED BY STRIK, BALDINELLI, MONIZ (SBM), PROJECT NUMBER SBM-21-1211, DATED MAY 2021.

SITE BENCHMARK

BENCHMARK#1:
MONUMENT TYPE: HYDRANT SPINDLE

LOCATION: TOP OF HYDRANT SPINDLE LOCATED ON THE SOUTHEAST CORNER OF THE SUBJECT SITE.

GEODETIC ELEVATION (CGVD2013): 98.77m

BENCHMARK#2:
MONUMENT TYPE: PK NAIL

LOCATION: PK NAIL IN ASPHALT AT NORTHWEST CORNER ON SITE ADJACENT TO ELGIN STREET WEST.

GEODETIC ELEVATION (CGVD2013): 104.16m

(CONTRACTOR TO CONFIRM BENCHMARK ELEVATIONS)



KEY PLAN

N.T.S.

LEGAL INFORMATION

PART OF
LOT 21, CONCESSION A
(GEOGRAPHIC TOWNSHIP OF HAMILTON)
IN THE
TOWN OF COBOURG
COUNTY OF NORTHUMBERLAND


ELGIN STREET WEST
EX. CB LID=103.08
EX. E/P
EX. CURB
EX. MH LID=102.
EX. ASPHALT MULTI-USE TRAIL
EX. SIGN
EX. HP
EX. GUYWIRE
EX. BELL PED(2)
EX. BELL PED
EX. CURB
EX. CONC. SWK
EXISTING BUILDING
EX. E/P
EXISTING PARKING
EX. SAMH LID=101.20 (150)NW.INV=99.61 (150)S.INV=99.59
EX. SAMH LID=99.93 (150)N.INV=98.30 (150)NW.INV=98.27 (150)S.INV=98.21
MUN# 1011 SHOPPING CENTRE COMMERCIAL (SC-4) ZONING
EX. LS
N18°12'00"W
205.72
EX. GARBAGE ENCLOSURE
BENCHMARK #1 ELEV=98.77
EX. SAMH LID=98.27 (150)N.INV=96.90 (150)S.INV=96.86
EX. CB LID=98.07 (200)N.INV=97.33
EX. HYD
EX. WV
EX. SAMH LID=97.76 (150)N.INV=96.18 (150)SW.INV=96.14
SOLID HATCH DENOTES EXTENT OF PROPOSED ASPHALT
CONSTRUCTION BOUNDARY
11.51
PROPOSED 6.0m FIRE ROUTE (126.5m)
3m X 6m CONCRETE PAD
PROPOSED 1.0m LANDSCAPED AREA
EX. LIGHT STANDARD TO BE RELOCATED
SPEAKER POST
MENU BOARD
PROP. BOLLARDS, 3 TYP., REFER TO DETAIL ON SP2
FR-3
BARRIER CURB TO OPSD 600.110
1.5m WIDE CONC S/W TO OPSD 310.020
PROPOSED BUILDING TOTAL AREA = 633.5m²
PROP. RESTAURANT AREA= 163.7m² F.F.E.=100.50
PROP. RESTAURANT AREA= 102.3m² F.F.E.=100.50
PROP. CRU AREA= 110.3m² F.F.E.=100.50
PROP. CRU AREA= 90.4m² F.F.E.=99.70
PROP. RESTAURANT AREA= 175.7m² F.F.E.=99.40
PFFE*/BARRIER FREE
PROPOSED LANDSCAPED AREA
LOADING AREA
DRIVE THROUGH ENTRANCE SIGN
PAVEMENT MARKINGS AS PER OPSS 710
EXISTING PARKING 69.36
PROPOSED LANDSCAPED AREA
STOP SIGN
EX. GUY WIRE TO BE RELOCATED
DEEP WELL GARBAGE AND RECYCLING UNITS ON CONCRETE PAD, SEE DETAIL ON SHEET SP2.
BENCHMARK #2 ELEV=104.16
1.8m WIDE CONC S/W TO OPSD 310.020
PROPOSED LANDSCAPED AREA
BARRIER CURB TO OPSD 600.110
PAINTED LINES TO OPSS 710, (TYP.)
CONSTRUCTION BOUNDARY
EX. SAMH LID=100.40 (150)SE.INV=98.61 (150)W.INV=98.58 (150)NW.INV=98.55
EX. LANDSCAPE ISLAND
EXISTING BUILDING
55.36m FROM EX. PRIVATE HYDRANT TO FIRE FIGHTER'S ENTRANCE
EX. HYD
EXISTING PARKING
SHOPPING CENTRE COMMERCIAL (SC-1) ZONING
EX. BOLLARD
EX. CB LID=98.34 FULL OF DIRT
EXISTING BOLLARD TO BE REMOVED DURING CONSTRUCTION AND RESTORED ONCE WORKS COMPLETE
CONTRACTOR TO ENSURE EXISTING BUILDING IS SUPPORTED AND NOT UNDERMINED DURING STORM SEWER WORKS
DOORSILL ELEV=99.04
EX. ASPHALT LOADING DOCK
EX. CONC.
EXISTING PARKING
EX. ASPHALT BREAKLINE
EXISTING BUILDING FFE=99.04M
50.54
EX. BOLLARDS(2)
EX. CONC. SWK
EX. CB LID=98.37 (300)S.INV=97.25 (225)W.INV=97.23(GALLERY?)
N18°39'30"W
205.74
37.11
47.16
EX. GAS METER
EX. BOLLARD
EXISTING BUILDING FFE=98.94M
EX. MISC.
EX. SAMH LID=97.45 (150)E.INV=95.83 (NW.INV)=95.55 (150)S.INV=95.52
EX. CB LID=97.07 (200)N.INV=95.88 (200)W.INV=95.20
EX. GUYWIRE
EX. STMH(DOGHOUSE) LID=97.14 (150)NW.INV=94.22 (150)N.INV=94.12 (150)S.INV=94.12
EX. SAMH LID=97.22 (150)N.INV=94.31 (250)N.INV=93.53(DROP) (250)S.INV=93.45
EX. GUYWIRE(4)
EX. HP(2)
EX. CB LID=95.76 (125)S.INV=95.13
61.30
N71°52'40"E
EX. BELL PED
EX. ASPHALT MULTI-USE TRAIL
EX. CURB
EX. E/P
EX. CBMH LID=103.53
EX. MISC. MH LID=103.54
EX. CB LID=103.46
EX. CB LID=103.46
EX. LS
EX. BELL PED
3m X 6m CONCRETE PAD
EX. LS
EX. HP
EX. SIGN
EX. BELL PED
EX. SIGN
EX. LS
EX. LS
EX. LS