

Plotted - November 25, 2020 File: Z: \Cima-C14\Projects\C14-0305-Terry Fox SWM Pond Cleanout (Cobourg)\400-Drawings and Sketches\410-WIP\AutoCAD\C14-0305 Terry Fox SWMP Quantities.dwg




TERRY FOX SWM POND CLEANOUT CONTRACT No. CO-21-03 PWD


TERRY FOX SWM POND

DRAWING INDEX	
DRAWING No.	TITLE
1	NOTES AND DETA
2	SITE PLAN
REFERENCE DRAWINGS	
GP8	STORMWATER DETENTI
PP11	OUTLET - DETENTION EASEMENT


KEY MAP N.T.S.



ISSUED FOR TENDER



N.T.S.



N.T.S.

GENERAL STAGING AND CONSTRUCTION NOTES

STAGE 1 - ACCESS, DEWATERING & FLOW MAINTENANCE

- A. PREPARE AND SECURE SITE ACCESS FROM FRASER COURT. PROTECT EXISTING ASPHALT AND CONCRETE SURFACES & SIDEWALK. TRIM BRANCHES AND REMOVE VEGETATION ALONG MAINTENANCE ACCESS ROUTE AS REQUIRED TO ALLOW EQUIPMENT PASSAGE WITHOUT DAMAGING EXISTING TREES AND SHRUBS. USE SHARP EQUIPMENT TO PROVIDE A CLEAN CUT OF BRANCHES AND ROOTS.
- PREPARE ACCESS ROUTE TO FACILITATE EQUIPMENT AND MATERIAL Β. ACCESS INCLUDING EXCAVATION, WOVEN GEOTEXTILE, 50mm CRUSHED LIMESTONE AND LIMESTONE SCREENINGS.
- ORGANIZE AND SCHEDULE THE WORKS FOR SUFFICIENT SUCCESSIVE C. DAYS OF FORECASTED DRY WEATHER CONDITIONS.
- ASSEMBLE COFFER DAMS AT INLETS TO ISOLATE FLOWS FROM PHASED D. WORK AREAS.
- INSTALL APPROPRIATELY SIZED FISH SCREEN IN A TRAPEZOIDAL E. CONFIGURATION IN FRONT OF OUTLET STRUCTURE AT WATER QUALITY RISER.
- DEWATERING SCHEMATIC TO BE PROVIDED TO CONTRACT F.
- ADMINISTRATOR 10 DAYS PRIOR TO COMMENCING DEWATERING. DRAW DOWN POND WATER LEVEL IN COORDINATION WITH G.
- ENVIRONMENTAL CONSULTANT RETAINED BY THE TOWN OF COBOURG. H. COLLECTION OF STRANDED FISH/WILDLIFE FROM POND. FISH SHALL BE HUMANELY DISPOSED OF ACCORDING TO MNRF DIRECTION, OTHER WILDLIFE SHALL BE APPROPRIATELY RELOCATED BY SPECIALIZED
- ENVIRONMENTAL CONSULTANT (TO BE COMPLETED BY OTHERS). PUMP ANY WATER (IF REQUIRED) TO FILTER BAGS LOCATED AT LEAST 30m FROM CREEK. PERIODICALLY PUMP WATER FROM THE POND TO FILTER BAGS AS REQUIRED TO KEEP THE POND DRY.

STAGE 2 - SEDIMENT REMOVAL

- A. PREPARE A SECURED AREA FOR SEDIMENT CONTAINMENT, DRYING AND/OR PROCESSING. SEDIMENT PROCESSING AREA MUST DRAIN TOWARDS THE SWM POND.
- Β. REMOVE SEDIMENT FROM SWM POND & FOREBAY AND RESTORE TO ORIGINAL GRADES (REFER TO DWG GP8).
- C. CLEAR SEDIMENT DEBRIS FROM INLET AND OUTLET PIPES. CLEANOUT CULVERTS CONNECTING FOREBAY TO POND. D.


STAGE 3 - SITE MAINTENANCE & SEDIMENT DISPOSAL

REMOVE BULK DEBRIS AND GARBAGE FROM SWM FACILITY. Α.

- Β. WATER QUALITY OUTLET - SEDIMENT IS PLUGGING THE WATER QUALITY RISER. REMOVE EXISTING CLEARSTONE JACKET SURROUNDING THE CSP RISER. REMOVE THE DAMAGED 1500mm CSP WATER QUALITY RISER AND LOCKABLE GRATE AND REINSTATE HICKENBOTTOM PVC DRAIN. REMOVE AND REPLACE THE CONCRETE SLAB FOUNDATION. INSTALL NEW 1,500mm CSP RISER. PLACE CLEAR STONE JACKET AROUND THE CSP WITH 50-80mm GRADED CLEAR STONE. REFER TO REFERENCE DRAWING PP11.
- C. TEST SEDIMENT USING THE TEST METHOD FOR THE DETERMINATION OF "LIQUID WASTE" (SLUMP TEST) AS DETAILED IN SCHEDULE 9 OF R.R.O 1990, Reg. 347 TO DETERMINE WHEN MATERIAL IS SUFFICIENTLY DRY AND CAN BE DISPOSED OF AS SOLID WASTE IN ACCORDANCE WITH R.R.O 1990, Reg. 347.
- D. REMOVE AND DISPOSE OF SOLIDIFIED SEDIMENT AT AN APPROVED LOCATION. TRANSPORT SEDIMENT BY APPROVED VENDORS AND EQUIPMENT.
- E. DECOMMISSION THE SEDIMENT CONTAINMENT, DRYING, PROCESSING AREA.
- F. CLEAN EXISTING ACCESS PATHWAY AND ALL EQUIPMENT UTILIZED. ENSURE ALL WATER DRAINS TOWARDS THE POND.
- G. RESTORATION OF ALL DISTURBED AREAS WITH TOPSOIL AND SEED.



ISSUED FOR TENDER



CONSTRUCTION TIMING

• ALL SWM POND CLEANOUT AND REHABILITATION WORKS TO BE COMPLETED FROM APRIL 15 TO SEPTEMBER 30.

CONSTRUCTION PHASES

• DEWATERING SCHEMATIC TO BE PROVIDED TO CONTRACT ADMINISTRATOR 10 DAYS PRIOR TO COMMENCING DEWATERING.

• REMOVE DEBRIS FROM WEIR AND OUTLET HEADWALL. ENSURE WEIR IS FUNCTIONAL AS IT WILL BE USED AS TEMPORARY OUTLET FOR PHASE 1. COFFERDAM INLETS OF CULVERTS BETWEEN FOREBAY AND POND.

 FLUSH CULVERTS BETWEEN FOREBAY AND POND. • PUMP STANDING POND WATER TO FILTER BAG.

REMOVE SEDIMENT FROM POND AREA.

REPLACE CSP RISER AND CLEARSTONE JACKET AROUND HICKENBOTTOM

WES

SCALE :

1:250

DATE :

NOVEMBER 2020

ELGIN STREET


• TRANSFER COFFER DAMS TO INLETS IN FOREBAY.


• PUMP INFLOW INTO FILTER BAG WHICH OUTLETS TO POND. BAG AND DISPOSE OF PHRAGMITES.

REMOVE SEDIMENT FROM FOREBAY AREA.

OZ HWY 401 ARIO ∕ທ, BURNH SITE Z (\mathcal{O}) ELGIN ST W key plan BM1 97.852 EAST CORNER OF TRANSFORMER FOOTING IS THE RESPONSIBILITY OF THE CONTRACTOR TO INFORM THEMSELVES OF THE EXACT LOCATION OF, AND ASSUME ALL LIABILITY FOR DAMAGE TO ALL UTILITIES SERVICES AND STRUCTURES WHETHER ABOVE GROUND OR BELOW GRADE BEFORE COMMENCING THE WORK. SUCH INFORMATION IS NOT NECESSARILY SHOWN ON THE DRAWING, AND WHERE SHOWN, THE ACCURACY CANNOT BE GUARANTEED. WITH THE SOLE EXCEPTION OF THE BENCHMARK(S) SPECIFICALLY DESCRIBED FOR THIS PROJECT, NO ELEVATION INDÍCATED OR ASSUMED HEREON IS TO BE USED AS A REFERENCE ELEVATION FOR ANY PURPOSE. ALL DIMENSIONS AND INFORMATION SHALL BE CHECKED AND VERIFIED ON THE JOB AND ANY DISCREPANCIES MUST BE REPORTED TO THE MUNICIPALITY BEFORE COMMENCING THE WORK. DRAWINGS ARE NOT TO BE SCALED. R. D. CRESSMA 100150917 RE-ISSUED FOR TENDER 25/11/2020 RC 15/01/2020 RC ISSUED FOR TENDER DATE BY **ISSUES / REVISIONS** Cobourg PROJECT: TERRY FOX SWM POND CLEANOUT DRAWING: SITE PLAN CHECKED BY : PROJECT DRAWN BY : R. CRESSMAN C14-0305 K. LUKAWIECKI DESIGNED BY : APPROVED BY : DRAWING No. R. CRESSMAN S. MAY **ISSUED FOR TENDER**

Ζ





the set of a set of the set of th

0+100	0+100
EVELOPMENT INC. DESIGN TO PEY CANADA LIMITED)	BY: BY: BY: BY: BY: BY: BY: BY: